

1 120620

9-9 15.185.01747.0000 69 R

API NUMBER 15- Drill Completion Date 9/7/57

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE NE, SEC. 27, T 21 S, R 13 W/E

4950 feet from S section line

990 feet from E section line

Lease Name Gates Well # 16

County Stafford

Well Total Depth 3700 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 250

Operator License # 30385

Operator: Liedtke Operating Corporation

Name & Address 370 17th St., Suite 5020

Denver, CO 80202

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____
Chase Well Service, Inc.

Plugging Contractor _____ License Number 6123

Address P.O. Box 355, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 9 Month: 9 Year: 19 91

Plugging proposal received from Charles Steincamp

(company name) Liedtke Operating Corporation (phone) 316-793-9556

were: 7" at 3700' w/200 sx cemetrn, PBTD 3610', Perfs at 3350-3668' (6 sets)

1st plug pump 150 lbs. hulls and 70 sx common cement 4% cc on bottom,

2nd plug perforate at 700' and circulate cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6 p.m. Day: 9 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT Ran tubing to 740' and circulated with 385 sx cement, both 7" and 10 3/4" circulated.

Pulled tubing and filled with 25 sx cement.

RECEIVED STATE CORPORATION COMMISSION

SEP 18 1991

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel and common cement by Allied. No casing recovery.

(if additional description is necessary, use BACK of this form.)

(did / did not) observe this plugging.

DATE 10-4-91

Signed _____ (TECHNICIAN)

INV. NO. 33264