

1 040836

4-7

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- #E-24,815 15-185-01746-0001

NE NE NE, SEC. 27, T 21 S, R 13 W XX

4950 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6170

Lease Name R.C. Gates Well # 15

Operator: Globe Exploration, Inc.

County Stafford

Name & Address P.O. Box 12

Well Total Depth 3650 118.62 feet

Great Bend, KS 67530-0012

Conductor Pipe: Size _____ feet

Surface Casing: Size 13 3/8 feet 252

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:15 a.m. Day: 7 Month: 4 Year: 19 94

Plugging proposal received from David Brady

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

logs: 7" at 3643' w/225 sx cement, BP 3626', Paris at 3312-86' (6 sets), Arbuckle open hole 3643-50'

1st plug sand back to 3260' and dump 7 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 175 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 7 Month: 4 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 3260' and dumped 7 sx cement on top of sand bridge through bailer,

2nd plug pumped down 13 3/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx gel, 100 lbs. hulls, and 175 sx cement.

RECEIVED STATE CORPORATION COMMISSION

APR 14 1994

Maximum pressure 700 psi and shut in 100 psi.

CONSERVATION DIVISION Wichita Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1600' of 7" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 4-21-94

Signed Stephen J. Pifer (TECHNICIAN)

INV. NO. 40315