

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-21164-00-01
Spot: NWNWSENE Sec/Twnshp/Rge: 9-26S-11W
1632 feet from N Section Line, 1013 feet from E Section Line
Lease Name: SHRIVER B Well #: 1
County: PRATT Total Vertical Depth: 4425 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3550		WITH 2 SX CMT.
PROD	5.5	4129	0	WITH 150 SX CMT
SURF	8.625	301		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/09/2017 10:20 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: TIM JULIAN Company: ABERCROMBIE ENERGY Phone: (620) 793-8185

Proposed
Plugging
Method:

2 SX CMT ON TOP OF BMD PACKER. CIBP @ 3550' WITH 2 SX CMT. LOAD & TEST CASING T 500#.
PERFORATE 5 1/2" AT 650'. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2017 3:50 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

RUN TBG TO 3908', PUMP 60 SX COMMON CMT 3% CC WITH 200# HULLS. WAIT 2 HOURS. LOAD HOLE. PRESSURE TO 300#. WOULD NOT HOLD. TAG WITH WIRELINE AT 3800'. SET CIBP @ 3550' WITH 2 SX CMT. LOAD HOLE & PRESSURE TO 250#. HOLDING. PERFORATE 4 SHOTS PER FOOT AT 610'. PUMP 200 SX CMT DOWN 5 1/2". CIRCULATED UP 5 1/2" X 8 5/8". TOP OFF WITH 25 SX CMT. 11/10/17: FELL 120'. TOPPED OFF WITH CMT.

Perfs:

Top	Bot	Thru	Comments
4028	4044		
3632	3637		
3598	3602		

INVOICED
JAN 09 2018

Remarks: USED COMMON CEMENT & 60/40 POZMIX 4% GEL BY COPELAND CEMENT.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
NOV 21 2017
KCC DODGE CITY