

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-21429-00-01

Spot: NWNWSE

Sec/Twnshp/Rge: 5-28S-32W

2750 feet from N Section Line, 2490 feet from E Section Line

Lease Name: COX

Well #: 1-5

County: HASKELL

Total Vertical Depth: 5579 feet

Operator License No.: 34289

Op Name: ADAMS AFFILIATES, INC.

Address: 1437 S. BOULDER, STE 930
TULSA, OK 74119

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5428		WITH 2 SX CMT

CIBP		5519		
------	--	------	--	--

PROD	5.5	5576	0	WITH 225 SX CMT
------	-----	------	---	-----------------

SURF	8.625	1945		WITH 950 SX CMT
------	-------	------	--	-----------------

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/18/2017 8:00 AM

Plug Co. License No.: 34059

Plug Co. Name: HURRICANE SERVICES, INC.

Proposal Rcvd. from: JENNIFER SEXTON

Company: ADAM AFFILIATES

Phone: (918) 582-4242

Proposed Plugging Method: SET CIBP @ 5420' WITH 2 SX CMT. PERFORATE AT 1980' WITH 50 SX CMT. PERFORATE AT 900' & CIRCULATE CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN

Witness Type: NONE

Date/Time Plugging Completed: 11/18/2017 12:30 PM

KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 5428' WITH 2 SX CMT. 1ST PLUG PERFORATE AT 1980' WITH 15 SX GEL & 50 SX CMT (100# HULLS IN BACK HALF). 2ND PLUG PERFORATE AT 900' & CIRCULATE 265 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
5530	5542		
5470	5485		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

INVOICED

JAN 02 2018

District: 01

Signed

K. Sullivan
JA
(TECHNICIAN)

RECEIVED

NOV 27 2017

KCC LODGE CITY