

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20826-00-00  
Spot: NWNWSESE Sec/Twnshp/Rge: 21-25S-40W  
1269 feet from S Section Line, 1217 feet from E Section Line  
Lease Name: DURLER Well #: 1-21  
County: HAMILTON Total Vertical Depth: 2590 feet

Operator License No.: 34289  
Op Name: ADAMS AFFILIATES, INC.  
Address: 1437 S. BOULDER, STE 930  
TULSA, OK 74119

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2540		
PROD	5.5	2589	0	WITH 525 SX CMT
SURF	8.625	308		WITH 108 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/30/2017 9:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: RIGO Company: HURRICANE SERVICES, INC. Phone: (316) 303-9515

Proposed Plugging Method: FILL THE 5 1/2" CASING WITH 150# HULLS IN THE FIRST PART OF APPROX. 250 SX CMT. PRESSURE TO 500#. FILL THE 5 1/2" X 8 5/8" ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/30/2017 4:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL CASING WITH CMT FROM 2506' TO 0' USING 150# HULLS & 290 SX CMT.  
PRESSURE TO 500#. HOLDING. PUMP 10 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
2551	2553		
2502	2506		

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE.


INVOICED

JAN 02 2018

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
DEC - 7 2017  
KCC DODGE CITY



JA