

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-22807-00-00  
Spot: SWNESENW Sec/Twnshp/Rge: 17-19S-21W  
3509 feet from S Section Line, 3049 feet from E Section Line  
Lease Name: STIEBEN Well #: 3  
County: NESS Total Vertical Depth: 4400 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4200		WITH 2 SX CMT
PROD	5.5	4399	0	WITH 125 SX CMT
SURF	8.625	461		WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/30/2017 9:30 AM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/30/2017 1:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4200' WITH 2 SX CMT. RAN BOND LOG. FOUND CMT 1390'-465'. SPOT 35 SX CMT AT 1500'. PERFORATE AT 450' & PUMPED 140 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4324	4334		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

INVOICED  
JAN 02 2018

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
DEC - 5 2017  
KCC DODGE CITY MD

JA