

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22728-00-00
Spot: NESESE Sec/Twnshp/Rge: 6-8S-21W
990 feet from S Section Line, 330 feet from E Section Line
Lease Name: GOSELIN Well #: 1
County: GRAHAM Total Vertical Depth: 3693 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3688		200 SX
SURF	8.625	272		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2017 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: OCTAVIO D MORALES Company: AMERICAN WARRIOR, INC. DBA Phone: (620) 275-2963

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar at 1677' w/400 sx cement.
Perforations: 3460' - 3462' and 3477' - 3480'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2017 2:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3290' and pumped 75 sx cement w/250 # hulls. Pulled tubing to 2302' and pumped 75 sx cement. Pulled tubing to 1301' and pumped 245 sx cement w/150 # hulls. Cement was not circulating well. Pulled tubing out and cement fell.
11/15/2017 - Topped off casing with 40 sx redi mix cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 150 psi.

GPS: 39.38243 -099.69730

Perfs:

KCC WICHITA
DEC 04 2017
RECEIVED

Remarks: SWIFT CEMENT TICKET # 30544

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

NOV 16 2017

Form CP-2/3