

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-22147-00-00
Spot: NENWNWSE Sec/Twnshp/Rge: 5-33S-6E
2421 feet from S Section Line, 2200 feet from E Section Line
Lease Name: HAMMER D Well #: 3
County: COWLEY Total Vertical Depth: 3160 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 3160 | | 125 SX |
| SURF | 8.625 | 204 | | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/11/2017 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY W ANSTINE Company: ANSTINE & MUSGROVE Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS/ CIBP SET @ 3055 W/ 2 SXS CEMENT. PERF & CIRCULATE 350'-0'.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 12/13/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, PERFORATED SQUEEZE HOLES 350'-351', (4 HOLES). 12-12-2017 RIH W/BIT & TUBING, CIRCULATING VARIOUS BRIDGES FROM 800'-1257'. LAYED DOWN TUBING & BIT. 12-13-2017 RIH W/TUBING @ 1250', QES ESTABLISHED CIRCULATION AND PUMPED 200 SXS CLASS A COMMON 2% CC W/ HULLS TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET #54848. SQUEEZED CEMENT ON BACKSIDE.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3101 | 3109 | CSG | |

INVOICED

Remarks: DENIED 10 YEAR TA

JAN 02 2018

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)