

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-115-20929-00-00  
Spot: NENESW Sec/Twnshp/Rge: 10-18S-1E  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: H I CHRISTIANSEN Well #: 2-10  
County: MARION Total Vertical Depth: 3305 feet

Operator License No.: 5920  
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G  
Address: PO BOX 522  
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3304		300 SX
SURF	8.625	207		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2017 2:15 PM  
Plug Co. License No.: 3038 Plug Co. Name: CYCLONE WELL SERVICE, INC.  
Proposal Revd. from: LUKE KOEHN Company: \_\_\_\_\_ Phone: (620) 755-3089

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/15/2017 2:15 PM KCC Agent: JERRY SPARLING

Actual Plugging Report:

RAN 2 7/8" TUBING IN HOLE TO BOTTOM TAGGED @ 3105'. PUMPED 35 SX COMMON CEMENT FOR BOTTOM PLUG. PULLED TUBING, RAN 1" TUBING DOWN BACKSIDE TO 268'. PUMPED 63 SX 60/40 POZMIX WITH 4% CC AND CIRCUALTED TO SURFACE. RAN 285' 2 7/8" TUBING IN HOLE AND PUMPED 35 SX COMMON CEMENT AND CIRCUALTED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3212	3214		CSG
3105	3109		CSG

INVOICED

JAN 02 2018

Remarks: COPELAND TICKET #44993

Plugged through: CSG

District: 02

Signed:   
(TECHNICIAN)