

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-165-00174-00-00  
Spot: SENENW Sec/Twnshp/Rge: 31-17S-16W  
4279 feet from S Section Line, 2967 feet from E Section Line  
Lease Name: ROTHE Well #: 1  
County: RUSH Total Vertical Depth: 3436 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2925		WITH 4 SX CMT
CIBP		3003		
PROD	7	3482	0	WITH 150 SX CMT
SURF	10.75	1094		WITH 500 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/21/2017 9:30 AM  
Plug Co. License No.: 99981 Plug Co. Name: COPELAND ACID & CEMENT, INC.  
Proposal Rcvd. from: NATHAN WOOD Company: COPELAND ACID & CEMENT, INC. Phone: (316) 524-1225

Proposed Plugging Method: CIBP @ 2925' WITH 4 SX CMT. PERFORATE AT 1130' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/21/2017 12:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 2925' WITH 4 SX CMT. PEFORATED AT 1130'. RAN TBG TO 1140'. CIRCULATED CMT INSIDE & OUTSIDE OF THE 7" WITH 425 SX CMT. PULLED TBG & TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2976	2990		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

INVOICED  
JAN 02 2018

Plugged through: TBG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
DEC - 5 2017  
KCC DODGE CITY [Signature]