

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-22181-00-01  
Spot: NESE Sec/Twnshp/Rge: 1-26S-15W  
1965 feet from S Section Line, 683 feet from E Section Line  
Lease Name: THOMPSON Well #: 1A  
County: PRATT Total Vertical Depth: 2225 feet

Operator License No.: 31093  
Op Name: BECKER OIL CORPORATION  
Address: PO BOX 1150  
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2015		WITH 2 SX CMT
PROD	4.5	2225	1570	WITH 150 SX CMT
SURF	8.625	291		WITH 250 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/21/2017 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: DOUG BROWN Company: BECKER OIL Phone: (620) 287-4724

Proposed Plugging Method: SET CIBP @ 2015' WITH 2 SX CMT. PLUG AT 1010' WITH 12 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/21/2017 4:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 2015' WITH 2 SX CMT ON TOP. 1ST PLUG AT 1010' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 75 SX CMT. CMT HOLDING AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
2192	2201		
2065	2096		

Remarks: USED 60/40 POZMIX 4% GEL BY GLOBAL OILFIELD SERVICES.


Plugged through: CSG

INVOICED

JAN 02 2018

District: 01

Signed



(TECHNICIAN)

RECEIVED  
NOV 22 2017  
KCC DODGE CITY



SA