

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23290-00-01
Spot: SESESW Sec/Twnshp/Rge: 23-17S-25W
339 feet from S Section Line, 2902 feet from E Section Line
Lease Name: SHEARER, JOHN C LEASE Well #: 4
County: NESS Total Vertical Depth: 4437 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	1741		WITH 375 SX CMT
PROD	5.5	4436	0	WITH 130 SX CMT
SURF	8.625	335		WITH 185 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/30/2017 1:30 PM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO LLC Phone: (316) 265-3311

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 50 SX CMT & 150# HULLS. PULL TBG TO 1760' & CIRCULATE CMT & HULLS TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2017 4:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4024' & PUMPED 50 SX CMT & 150# HULLS. PULLED TBG TO 1760' & PUMPED 150 SX CMT WITH 550# HULLS. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
4420	4424		
4320	4324		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

Plugged through: TBG

District: 01

Signed Michael Maier
MA (TECHNICIAN)

RECEIVED
DEC - 5 2017
KCC DODGE CITY