

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23634-00-00
Spot: E2NWNENE Sec/Twnshp/Rge: 1-7S-22W
330 feet from N Section Line, 970 feet from E Section Line
Lease Name: THURLOW Well #: 1-1
County: GRAHAM Total Vertical Depth: 3791 feet

Operator License No.: 33306
Op Name: BLAKE EXPLORATION, LLC
Address: 201 S MAIN PO BOX 150
BOGUE, KS 67625

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3787		240 sx
SURF	8.625	208		150 SX
T1	2.375	3735		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2017 11:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: MIKE DAVIGNON Company: BLAKE EXPLORATION, LLC DBA Phone: (785) 421-2921

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% w/200 # hulls.
Port Collar at 1926' w/210 sx cement.
Perforations: 3486' - 3489' and 3556' - 3560'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/16/2017 1:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied on to casing and pumped 50 sx cement w/200 # hulls, followed by 12 sx gel, followed by 170 sx cement. Shut in pressure 500 psi. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 200 psi.

GPS: 39.48010 -099.71671

Perfs:

Top	Bot	Thru	Comments
3556	3560		
3486	3489		
3467	3471		

KCC WICHITA
DEC 04 2017
RECEIVED


INVOICED
JAN 02 2018

Remarks: QUALITY CEMENT TICKET # 346

Plugged through: CSG

District: 04

Signed


(TECHNICIAN)

CM