

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-21503-00-00  
Spot: SESEWNNE Sec/Twnshp/Rge: 32-23S-13E  
4160 feet from S Section Line, 1520 feet from E Section Line  
Lease Name: BILL BERRY Well #: 1-H  
County: GREENWOOD Total Vertical Depth: 1704 feet

Operator License No.: 34827  
Op Name: C3OIL, LLC  
Address: 600 ARROWHEAD DR  
NEW STRAWN, KS 66839

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 3     | 1742       |             | 51 SX    |
| SURF   | 8.625 | 40         |             | 18 SX    |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/14/2017 12:00 PM  
Plug Co. License No.: 33413 Plug Co. Name: TITUS WELL SERVICE LLC  
Proposal Rcvd. from: CHRIS HAAS Company: \_\_\_\_\_ Phone: (913) 515-5329

Proposed Plugging Method: Casing was perforated at 600' and 250'. Run 2 3/8 tubing to TD. Pulled back to 1658. Set 10 sack plug on bottom of casing. Pull tubing to 600' set 10 sack plug at 600'. Pull tubing to 250'. Cement from 250' to top of casing.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/14/2017 2:30 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1575', pumped 25 sxs cement, pulled tubing to 600' pumped 15 sxs cement, pulled tubing to 250' pumped 60 sxs cement to surface. gel spacers between cement plugs.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 1694 | 1714 |      |          |

RECEIVED  
KCC DIST #3  
DEC 18 2017  
CHANUTE, KS  
MH

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern  
(TECHNICIAN)

INVOICED  
JAN 02 2018

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



15-073-21503  
 Cement or Acid Field Report  
 Ticket No. **3674**  
 Foreman Kevin McCoy  
 Camp Eureka

| Date                                 | Cust. ID # | Lease & Well Number | Section                          | Township | Range    | County | State  |
|--------------------------------------|------------|---------------------|----------------------------------|----------|----------|--------|--------|
| 12-14-17                             | 1021       | BILL BERRY # 1-n    |                                  |          |          | Gw     | Ks     |
| Customer<br>C3 OIL                   |            |                     | Safety Meeting<br>KM<br>RL<br>AB | Unit #   | Driver   | Unit # | Driver |
| Mailing Address<br>600 ARROWHEAD DR. |            |                     |                                  | 102      | RICK L.  |        |        |
| City<br>New STRAWN                   |            |                     |                                  | 113      | ALLEN B. |        |        |
| State<br>KS                          |            |                     |                                  |          |          |        |        |
| Zip Code<br>66839                    |            |                     |                                  |          |          |        |        |

Job Type P.T.A. old well Hole Depth \_\_\_\_\_ Slurry Vol. 25 BBL Tubing 2 7/8  
 Casing Depth \_\_\_\_\_ Hole Size \_\_\_\_\_ Slurry Wt. \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. \_\_\_\_\_ Cement Left in Casing 1608' Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: SAFETY Meeting: 2 7/8 Set @ 1575' inside of 5 1/2 AND Cemented to SURFACE. Bottom of 5 1/2 casing @ 1600'. Ran 1" Hydrill Tubing to T.D. of 1608'. Spot 25 SKS CLASS "A" Cement w/ 2% Gel @ 1608'. Pull 1/2 of 1" Tubing. Finish Filling up 2 7/8 w/ Cement to SURFACE w/ 20 SKS. Pull 1" Tubing. Rig up to 2 7/8 Tubing. Squeeze 55 SKS Cement down 2 7/8 Tubing. FINAL Squeeze Pressure = 500 PSI. Shut in @ 300 PSI. Job Complete. Rig down.

| Code             | Qty or Units | Description of Product or Services | Unit Price | Total   |
|------------------|--------------|------------------------------------|------------|---------|
| C 105            | 1            | Pump Charge                        | 750.00     | 750.00  |
| C 107            | 25           | Mileage                            | 3.95       | 98.75   |
| C 200            | 100 SKS      | CLASS "A" Cement                   | 15.00      | 1500.00 |
| C 206            | 200 *        | Gel 2%                             | .20 *      | 40.00   |
| C 108 A          | 4.7 TONS     | TON Mileage                        | M/C        | 345.00  |
| <u>THANK You</u> |              |                                    | Sub Total  | 2733.75 |
| <u>M</u>         |              |                                    | Less 5%    | 146.94  |
|                  |              |                                    | Sales Tax  | 205.03  |
|                  |              |                                    | 7.5%       |         |

Authorization witnessed By CHRIS HAAS Title \_\_\_\_\_ Total 2791.84  
KCC AGENT MIKE HEFFERN

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.