

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-10077-00-00
Spot: SWNW Sec/Twnshp/Rge: 33-26S-34W
3293 feet from S Section Line, 4540 feet from E Section Line
Lease Name: PLEASANT PRAIRIE UNIT Well #: 41
County: FINNEY Total Vertical Depth: 5200 feet

Operator License No.: 34997
Op Name: CASILLAS PETROLEUM CORP
Address: 348 RD DD
SATANTA, KS 67870

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4950		WITH 2 SX CMT
DVT	5.5	2913		WITH 350 SX CMT
PROD	5.5	5190	0	WITH 600 SX CMT
SURF	8.625	806		WITH 425 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/28/2017 9:00 AM
Plug Co. License No.: 30921 Plug Co. Name: MEDINA WELL SERVICE, INC.
Proposal Rcvd. from: KENT PENDERGRAFT Company: CASILLAS PETROLEUM Phone: (620) 287-4060

Proposed Plugging Method: SET CIBP @ 4950' WITH 2 SX CMT. RUN CBL TO DETERMINE HOW TO PLUG.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/28/2017 12:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4950' WITH 2 SX CMT. LOAD HOLE & TEST CASING TO 300 PSI HOLDING. RAN CBL & FOUND TOC @ 810'. RTIH TO 1914' & SPOT 35 SX CMT. PERFORATE AT 795' & PUMP 200 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
5133	5140		


INVOICED
JAN 02 2018

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED COMMON CEMENT BY BASIC ENERGY SERVICES.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
NOV 29 2017
KCC DODGE CITY



JA