

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26895-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 15-13S-17W
1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: L J DREILING Well #: 2
County: ELLIS Total Vertical Depth: 3620 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: PO BOX 583
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	209		150 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/14/2017 12:00 AM
Plug Co. License No.: 34743 Plug Co. Name: WHITE KNIGHT DRILLING LLC
Proposal Rcvd. from: TERRY Company: WHITE KNIGHT DRILLING LLC Phone: (785) 303-8005

Proposed Plugging Method: Ordered 290 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CHRIS NEELEY Witness Type: NONE
Date/Time Plugging Completed: 11/14/2017 3:00 AM KCC Agent: CHRIS NEELEY

Actual Plugging Report:

1st plug @3520 w/50 sx
2nd plug @1220 w/50 sx
3rd plug @620 w/100 sx
4th plug @260 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx

Perfs:

KCC WICHITA
DEC 04 2017
RECEIVED


INVOICED
JAN 02 2018

Remarks: GLOBAL

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

NOV 17 2017