

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25991-00-00
Spot: W2NWNESW Sec/Twnshp/Rge: 13-16S-12W
2310 feet from S Section Line, 1335 feet from W Section Line
Lease Name: DOLECHECK Well #: 1
County: BARTON Total Vertical Depth: 3399 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: PO BOX 583
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3398	1710	150 SX
SURF	8.625	354		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/05/2017 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JERRY GREEN Company: CASTLE RESOURCES, INC. DBA Phone: (785) 625-5155

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/05/2017 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with cement. Cut casing. Pulled casing to 1450' and pumped 125 sx cement w/300 # hulls. Pulled casing to 800' and pumped 40 sx cement w/100 # hulls. Pulled casing to 400' and pumped 40 sx cement w/100 # hulls. Pulled casing to 200'. Circulated cement to surface with 25 sx cement. Pulled casing and hole stayed full.

GPS: 38.65858 -098.60384

Perfs:

Top	Bot	Thru	Comments
3350	3358		
3336	3342		
3123	3126		
3082	3085		
2962	2965		

INVOICED

JAN 02 2018

Remarks: GLOBAL CEMENTING

Plugged through: CSG

District: 04

Received
KANSAS CORPORATION COMMISSION

Signed Bruce Rodie
(TECHNICIAN)

CM

DEC 20 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3