

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-19372-00-00  
Spot: N2SWNE Sec/Twnshp/Rge: 19-29S-8E  
1650 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: SHINN Well #: 4  
County: BUTLER Total Vertical Depth: 2805 feet

Operator License No.: 33192  
Op Name: CROWN ENERGY COMPANY  
Address: 1117 N.W. 24TH ST.  
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2770		60 SX
SURF	10.75	19		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2017 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICK HART/HAYS WILSON Company: CROWN ENERGY CO Phone: (405) 526-0111

Proposed Plugging Method: AS PER KCC RULES & REGS/ CIBP @ 2750 W 5/SXS PERF & CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE  
Date/Time Plugging Completed: 11/06/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CUT TUBING @ 2480', LAYED TUBING DOWN. SET BRIDGE @ 2450' BAILED 2 SXS CEMENT ON TOP OF PLUG. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES @ 250'-251'. RIH W/TUBING @ 250', PUMPED 60 BBL WATER, NO CIRCULATION. MIXED & PUMPED 50 SXS CLASS A COMMON 3% CC & 100 # HULLS. NO RETURNS. LAYED TUBING DOWN. RIH W/TUBING @ 270', QWS MIXED & PUMPED 65 SX CLASS A COMMON CEMENT CIRCUALTED IN 5 1/2" CASING. LAYED DOWN TUBING, SWEDGED INTO 5 1/2" CASING, QWS MIXED & PUMPED 85 SXS CLASS A COMMON. NO CIRCULATION. RIH W/ TUBING @ 330'. QWS PUMPED 150# HULLS & 3 BAGGS OF CEDAR FIBER, 75 SXS CLASS A COMMON 3% CC TO SURFACE. CEMENT CIRCUALTED. TOPPED WELL BACK TO SURFACE WITH 10 SXS .

Perfs:

Top	Bot	Thru	Comments
2770	2805	OH	

INVOICED  
JAN 02 2018

Remarks: DENIED TA/ DUE TO LENGTH OF TIME

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

JK