

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-21236-00-02
Spot: NENESE Sec/Twnshp/Rge: 29-17S-27W
2331 feet from S Section Line, 326 feet from E Section Line
Lease Name: OPAL MCBEE (HORCHEM) Well #: 1-13
County: LANE Total Vertical Depth: 4580 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4495		
PROD	5.5	4626	0	WITH 250 SX CMT
SURF	8.625	423		WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/08/2017 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: AVEN WEAVERLING Company: DAMAR RESOURCES Phone: (785) 625-0020

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 100# HULLS. LOG HOLE. IF CMT ON BACKSIDE SPOT CMT AT ANHYDRITE THEN AT PERMIAN TO SURFACE, 50 SX CMT FOR BACKSIDE. IF NO CMT ON BACKSIDE WILL NEED TO PERFORATE AT ANHYDRITE & PERMIAN PLUS CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/08/2017 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 3600' & SPOTTED 35 SX CMT & 100# HULLS. THE HOLE WAS SANDED IN TO 3600'. THEY TRIED TO GET DOWN BUT WENT OUTSIDE CASING. RAN LOG & FOUND CMT 200' DOWN TO 900' THEN 1500' TO 2300'. RUN TBG TO 2100' & PUMPED 85 SX CMT & 400# HULLS. PULLED TBG TO 1100' & PUMPED 100 SX CMT & 500# HULLS. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4573	4577		
4449	4455		
4163	4306		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

INVOICED
JAN 02 2018

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)
SA

RECEIVED
DEC 12 2017
KCC DODGE CITY