

1060183

STATE CORPORATION COMMISSION

API NUMBER 15-135-22,920-0000  
NW SW SE SEC. 17, T 20 S, R 23 W

CONSERVATION DIVISION - PLUGGING SECTION 990 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BRANDT WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY NESS 143.65

OPERATOR LICENSE # 30269

WELL TOTAL DEPTH 4420 FEET

OPERATOR: ARGENT ENERGY, INC.

PRODUCTION CSG: SIZE 4 1/2" @ 4425' WITH 200 SX

NAME AND 110 S MAIN, SUITE 810

SURFACE CASING: SIZE 8 5/8" @ 513' WITH 280 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SWIFT SERVICES INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 11:30 AM DAY: 29 MONTH: 12 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) SWIFT SERVICES INC (PHONE) 785-798-2300

WERE: PERFS AT 4347-51

BOTTOM PLUG PUMP 30 SX CEMENT AND 200# HULLS. PRESSURED TO 850#. SHUT DOWN. PERFORATED

AT 700'. PUMPED 120 SX CEMENT ON STRONG VACUUM. MIXED 100 SX CEMENT WITH 200# HULLS.

PRESSURED TO 200# AND SHUT IN. WENT DOWN BACKSIDE PRESSURED RIGHT UP. NO CEMENT.

INVOICED

DATE 1/10/00  
06/083

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 29 MONTH: 12 YEAR: 1999

ACTUAL PLUGGING REPORT

BOTTOM PLUG PUMP 30 SX CEMENT AND 200# HULLS. PRESSURED TO 850#. SHUT DOWN. PERFORATED

AT 700'. PUMPED 120 SX CEMENT ON STRONG VACUUM. MIXED 100 SX CEMENT WITH 200# HULLS.

PRESSURED TO 200# AND SHUT IN. WENT DOWN BACKSIDE PRESSURED RIGHT UP. NO CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED STATE CORPORATION COMMISSION  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED

Michael J Maier  
(TECHNICIAN)

RECEIVED

JAN 05 2000

FORM C CONSERVATION DIVISION  
Wichita, Kansas