

1060184

TO: STATE CORPORATION COMMISSION

API NUMBER 15-135-22,787.0000
SW NW SE SEC. 17, T 20 S, R 23 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BRANDT WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY NESS \$143.81

OPERATOR LICENSE # 30269

WELL TOTAL DEPTH 4425 FEET

OPERATOR: ARGENT ENERGY, INC.

PRODUCTION CSG: SIZE 4 1/2" @ 4419' WITH 150 SX

NAME AND 110 S MAIN, SUITE 810

SURFACE CASING: SIZE 8 5/8" @ 520' WITH 250 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SWIFT SERVICES INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 12:00 PM DAY: 29 MONTH: 12 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) SWIFT SERVICES INC (PHONE) 785-798-2300

WERE: PERFS AT 4344-50

BOTTOM PLUG PUMP 30 SX CEMENT AND 200# HULLS PUMPED TO BOTTOM. PRESSURED TO 1800#.

PERFORATED AT 700'. PUMPED 120 SX CEMENT THEN HOOKED ONTO BACKSIDE AND PUMPED 30 SX

CEMENT. PRESSURED TO 650#. SHUT IN WITH 650#.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 1:30 PM DAY: 29 MONTH: 12 YEAR: 1999

ACTUAL PLUGGING REPORT

BOTTOM PLUG PUMP 30 SX CEMENT AND 200# HULLS PUMPED TO BOTTOM. PRESSURED TO 1800#.

PERFORATED AT 700'. PUMPED 120 SX CEMENT THEN HOOKED ONTO BACKSIDE AND PUMPED 30 SX

CEMENT. PRESSURED TO 650#. SHUT IN WITH 650#.

REMARKS: USED 160/40 PDZ MIX (6%) GEL BY SWIFT SERVICES. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING

INV. NO. 061083

SIGNED Michael J. Maier CONSERVATION DIVISION (TECHNICIAN) FORM CP-2/Wichita, Kansas

RECEIVED STATE CORPORATION COMMISSION JAN 05 2000