

To: 1-070015
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

8-17

API NUMBER 15-135-24,020.0000
SW SE SW, SEC. 16, T 20 S, R 23 W XX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5228
Operator: Parrish Corporation
Name & Address: 110 S. Main, Ste. 510
Wichita, KS 67202

330 feet from S section line
1650 feet from WXX section line
Lease Name Valdah Well # 1
County Ness 144.63
Well Total Depth 4450 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 733

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor L.D. Drilling License Number 6039
Address RR 1, Box 183-B, Great Bend, KS 67530

Company to plug at: Hour: _____ Day: 17 Month: 8 Year: 1997

Plugging proposal received from Greg Davidson
(company name) L.D. Drilling (phone) 316-793-3051

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1520-40'
1st plug at 1550' with 50 sx cement,
2nd plug at 760' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Scott Alberg (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:45 p.m. Day: 17 Month: 8 Year: 1997

ACTUAL PLUGGING REPORT 1st plug at 1550' with 50 sx cement,
2nd plug at 760' with 50 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement.

RECEIVED
KANSAS CORPORATION COMMISSION
8-19-97
AUG 19 1997
CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 21 1997
INV. NO. 48836

Signed Scott Alberg (TECHNICIAN)

FOR KCC USE:

FORM MUST BE TYPED

EFFECTIVE DATE: 8-4-97

State of Kansas 135-24,020

FORM MUST BE SIGNED

DISTRICT #

NOTICE OF INTENTION TO DRILL

ALL BLANKS MUST BE FILLED

SEA7... Yes No

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date: 8/6/97
month day year

Spot East
SW SE SW Sec 16 Twp 20 S, Rg 23 West

OPERATOR: License # 5228
Name: Parrish Corp.
Address: 110 S Main #510
City/State/Zip: Wichita, KS 67202
Contact Person: Lloyd Parrish
Phone: 316-263-8726

330 feet from South North line of Section
1150 feet from East / West line of Section
IS SECTION REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 6039
Name: L.D. Drilling

County: Ness
Lease Name: Valda
Field Name: Pawnee Valley

Is this a Prorated/Spaced Field? yes no

Target Formation(s): Chero... Sd... Miss... Ft. Scott

Nearest lease or unit boundary: 330

Ground Surface Elevation: Approx. 2270 feet MSL

Water well within one-quarter mile: yes no

Public water supply well within one mile: yes no

Depth to bottom of fresh water: 150 180

Depth to bottom of usable water: 550 680 PERMIAN

Surface Pipe by Alternate: 1 2

Length of Surface Pipe Planned to be set: 600 700 MIN.

Length of Conductor pipe required:

Projected Total Depth: 4400

Formation at Total Depth: 4400 Mississippi

Water Source for Drilling Operations:

... well ... farm pond other

Well Drilled For: Well Class: Type Equipment:
 Oil ... Enh Rec ... Infield Mud Rotary
... Gas ... Storage Pool Ext. ... Air Rotary
... OAWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
... Other

If OAWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes no

If yes, true vertical depth:

Bottom Hole Location:

Will Cores Be Taken? yes no

If yes, proposed zone:

700' Alt. I Req.

Exp. 1/30/98

AFFIDAVIT

RECEIVED

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with all applicable rules and regulations of the Kansas State Board of Geology.

It is agreed that the following minimum requirements will be met:

Pusher: Bug Davidson INIT. mbw

SPUD DATE: 8-9-97 INIT. mbw

LENGTH SURFACE PLANNED: 200'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE

SURFACE PIPE 8 3/4" 7.33 CONDUCTOR

ANHYDRITE T- 1520 B- 1540 ELEVATION

TD 4450 FORMATION M.S.S

RAN PIPE @ SX DV TOOL @ SX ALT II DONE Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1550 Ft. W/ 50 SX

1/2 Base Anyh. @ Ft. W/ SX

1/2, 1/2 Plug @ Ft. W/ SX

Bottom Surface @ 760 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ X SX

WATER WELL SX (Irr. Well Pond Hauling X)

TECHNICIAN SA DATE 8-15-97

TYPE OF CEMENT 60/40 6% GY # FS

STARTING TIME (AM/PM) DATE

COMPLETION TIME 12:45 AM/PM DATE 8-17-97

CEMENT COMPANY Allied