

To: 1120578
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
207 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

6-12 158
API NUMBER 15- 135-23,581-0000

C NE, SEC. 1, T 20 S, R 23 W XX
3960 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 3007

Lease Name Riverside Well # 1

Operator: Western Kansas Exploration
Name & Address P.O. Box 126
Hays, KS 67601

County Ness 144.30

Well Total Depth 4440 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 214

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Western Kansas Drilling License Number 4083

Address P.O. Box 126, Hays, KS 67601

Company to plug at: Hour: 10 a.m. Day: 12 Month: 6 Year: 19 91

Plugging proposal received from Nancy

(company name) Western Kansas Drilling (phone) 913-628-2296

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1520-74'
1st plug at 1590' with 50 sx cement, 2nd plug at 800' with 80 sx cement,
3rd plug at 240' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4 p.m. Day: 12 Month: 6 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1590' with 50 sx cement,

2nd plug at 800' with 80 sx cement,

3rd plug at 240' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1991

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Halliburton.

(if additional description is necessary, use BACK of this form.)

INVOICED

~~did not~~ observe this plugging.

DATE 7-8-91

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 32261

15.135.23581.0000

EFFECTIVE DATE: 6-8-91

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas 135-23,581

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: 06/04/91
month day year

C NE Sec 01 Twp 20 S Rg 23

OPERATOR: License # 3007
Name: WESTERN KANSAS EXPLORATION
Address: P.O. BOX 126
City/State/zip: HAYS, KS 67601
Contact Person: STAN YOUNGER
Phone: 913-628-2296

3960 feet from South Line of Section
1320 feet from East Line of Section
(Note: Locate well on Section Plat on Reverse Side)

County: NESS
Lease Name: RIVERSIDE Well# 1
Field Name: UNKNOWN

CONTRACTOR: License # 4083
Name: WESTERN KANSAS DRILLING

Is this a Prorated Field? yes no

Target Formation(s): MISSISSIPPI

Nearest lease or unit boundary: 1320

Ground Surface Elevation: 2272 feet MSL

Domestic well within 330 feet: yes no

Municipal well within one mile: yes no

Depth to bottom of fresh water: 260

Depth to bottom of usable water: 875

Surface Pipe by Alternate: 1

Length of Surface Pipe Planned to be set: 200

Length of Conductor Pipe required:

Estimated Total Depth: 4450

Formation at Total Depth: MISSISSIPPI

Water Source for Drilling Operations: well farm pond other

DNR Permit#

If OWWO; old well information as follows:
Operator:
Well Name:
Comp Date: Old Total Depth:

RECEIVED

STATE CORPORATION COMMISSION

JUN 17 1991

CONSERVATION DIVISION

Will Cores Be Taken? yes no

If yes, proposed zone:

Exp. 12/3/91
The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 200' Alt. 2 Req.

AFFIDAVIT

581

Pusher Nancy
SPUD DATE 6-7-91 INIT Sm

LENGTH SURFACE PLANNED 200'

RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 1/2" @ 214 CONDUCTOR
ANHYDRITE T- 1520 B- 700 ELEVATION

TD 4440 FORMATION Miss

RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 1500 Ft. W/ SX

1/2 Base Anhy. @ 800 Ft. W/ SX

1/2, 1/2 Plug @ Ft. W/ SX

Bottom Surface @ 240 Ft. W/ SX

40' Plug @ 40 Ft. W/ SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond Hauling)

TECHNICIAN DR DATE 6-11-91

TYPE OF CEMENT 100-90-670 475.

STARTING TIME 10:00 (AM/PM) DATE 6-12-91

COMPLETION TIME 4:00 (AM/PM) DATE 6-12-91

CEMENT COMPANY H-c-11-b-1-for