

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-22312-00-00
Spot: N2SENESE Sec/Twnshp/Rge: 28-29S-15W
1901 feet from S Section Line, 301 feet from E Section Line
Lease Name: WESTERMAN Well #: 1-28
County: PRATT Total Vertical Depth: 4900 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN ST, STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4550		WITH 2 SX CMT
PROD	4.5	4898	2002	WITH 175 SX CMT
SURF	8.625	422		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2017 10:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (316) 646-4801

Proposed Plugging Method: CIBP @ 4550' WITH 2 SX CMT. PLUG AT 890' WITH 15 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/06/2017 11:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4550' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 894 WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 448' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 12/8/17: TG TPC @ 143'. WILL TOP OFF WITH 2 YARDS OF READY MIX.

Perfs:

Top	Bot	Thru	Comments
4682	4692		
4602	4612		

INVOICED
JAN 10 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
DEC - 8 2017
KCC DODGE CITY