

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-22902-00-00
Spot: N2NESESE Sec/Twnshp/Rge: 24-16S-26W
1069 feet from S Section Line, 308 feet from E Section Line
Lease Name: NICHEPOR Well #: 7
County: NESS Total Vertical Depth: 4571 feet

Operator License No.: 33984
Op Name: LUTZ, SCOTT T. TRUST
Address: PO BOX 1766
FAYETTEVILLE, AR 72702

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	1800		CEMENTED WITH 400 SX CMT
PROD	5.5	4569	0	WITH 200 SX CMT
SURF	8.625	302		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/07/2017 12:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: KENNY RUPP Company: SCOTT T LUTZ TRUST Phone: (785) 798-5260

Proposed Plugging Method: TBG TO BOTTOM & SPOT 50 SX CMT & 200# HULLS. SPACER TO 1800' THEN CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/08/2017 4:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4330' & PUMPED 50 SX CMT & 200# HULLS. PULLED TBG TO 1819' & PUMPED 210 SX CMT & 300# HULLS. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 40 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4516	4520		

INVOICED
JAN 10 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

Michael Maier

(TECHNICIAN)

RECEIVED
DEC 12 2017
KCC DODGE CITY

MP

SR