

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-24053-00-00  
Spot: W2NENENE Sec/Twnshp/Rge: 22-15S-14W  
330 feet from N Section Line, 425 feet from E Section Line  
Lease Name: OCHS "A" Well #: 5  
County: RUSSELL Total Vertical Depth: 3400 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3398	2370	160 SX
SURF	8.625	516		225 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/13/2017 8:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: BRENT HOMEIER Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 445-2353

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/13/2017 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Sanded off perforations and bailed 5 sx cement on top. Cut casing at 2370'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 520' and pumped 50 sx cement w/100 # hulls. Pulled casing to 250' and pumped 60 sx cement. Circulated cement back to pit. POOH. Cellar stayed full.

GPS: 38.73945 -098.85736

Perfs:

Top	Bot	Thru	Comments
3321	3325		

KCC WICHITA  
DEC 04 2017  
RECEIVED

INVOICED  
JAN 10 2018

Remarks: QUALITY CEMENTING TICKET # 447

Plugged through: CSG

District: 04

Signed Ray A Dinkel  
(TECHNICIAN)

CM

NOV 14 2017