

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-25462-00-00  
Spot: SWSNENW Sec/Twnshp/Rge: 27-17S-15W  
1150 feet from N Section Line, 2250 feet from W Section Line  
Lease Name: KELLY MANETH Well #: 2  
County: BARTON Total Vertical Depth: 3610 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3607	2400	160 SX
SURF	8.625	1045		350 SX
T1	2.875	3564		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/10/2017 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 483-2169

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/10/2017 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with 5 sx cement. Cut casing at 2400'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 1000' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 200' and pumped 80 sx cement. Circulated cement to surface. Pulled casing and hole stayed full.

GPS: 38.54788 -098.97019

Perfs:

Top	Bot	Thru	Comments
3552	3556		
3458	3463		
3444	3450		
3349	3353		
3314	3318		

KCC WICHITA  
DEC 04 2017  
RECEIVED

INVOICED  
JAN 10 2018

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

cm

NOV 20 2017

Form CP-2/3