

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-25968-00-00  
Spot: SWNENWSW Sec/Twnshp/Rge: 4-17S-13W  
2200 feet from S Section Line, 725 feet from W Section Line  
Lease Name: BARNGROVER Well #: 1  
County: BARTON Total Vertical Depth: 3423 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3421	2430	150 SX
SURF	8.625	516		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/29/2017 10:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 483-2169

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/29/2017 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded back to 2900' and topped with 5 sx cement. Pulled casing to 1450' and pumped 120 sx cement w/300 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 500' and pumped 40 sx cement w/100 # hulls. Pulled casing to 200' and pumped 55 sx cement. Circulated cement to surface. Pulled casing and hole stayed full.

GPS: 38.60031 -098.77306

Perfs:

Top	Bot	Thru	Comments
3364	3368		
3351	3354		

INVOICED  
JAN 20 2018

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

DEC 20 2017

CONSERVATION DIVISION  
WICHITA, KS

DEC 01 2017

Form CP-2/3