

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-00392-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 16-23S-34W  
3002 feet from S Section Line, 2283 feet from E Section Line  
Lease Name: GARDEN C Well #: 2  
County: FINNEY Total Vertical Depth: 2654 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY, LLC  
Address: 13727 NOEL ROAD, SUITE 1200  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1102		
PROD	7	2640	0	WITH 900 SX CMT
SURF	10.75	594		WITH 425 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/14/2017 1:00 PM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: DAVID Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/16/2017 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TOP OF 2 3/8" TBG FISH AT 1616'. ATTEMPT TO FISH TBG WITH OVERSHOT. COULD NOT. RAN 2 3/8" TBG TO 1965' ALONG SIDE THE TBG FISH. PULL TBG TO 1872' & SPOT 150 SX CMT. NO CIRCULATION. SDON. 11/16/17: RAN 7" JUNK BASKET. TAGGED TOF @ 1616'. NO CMT. RUN TBG TO 1590' & SPOT 50 SX CMT. SET CIBP @ 1102'. RUN CBL FROM 1100' TO 5'. FOUND TOC BEHIND 7" AT 5'. RUN TBG TO 1100' & CIRCULATE CMT TO SURFACE WITH 230 SX CMT. TOP OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2520	2624		
2460	2498		


INVOICED  
JAN 10 2018

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED CLASS C COMMON CMT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
NOV 27 2017  
KCC DODGE CITY



JA