

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-05181-00-00
Spot: SENWNW Sec/Twnshp/Rge: 16-1S-34W
990 feet from N Section Line, 990 feet from W Section Line
Lease Name: CAHOJ (TEXACO) Well #: 30
County: RAWLINS Total Vertical Depth: 4355 feet

Operator License No.: 30606 String Size Depth (ft) Pulled (ft) Comments
Op Name: MURFIN DRILLING CO., INC. PROD 5.5 4352 250 SX
Address: 250 N WATER STE 300 SURF 8.625 450 300 SX
WICHITA, KS 67202

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/20/2017 9:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Revd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 500 sx 60/40 pozmix 4% gel cement, 600 # gel and 1000 # hulls.
8 5/8" surface casing set at 450' w/300 sx cement.
5 1/2" production casing set at 4352' w/250 sx cement.
TD 4355', PBSD 4309'.
Perforations: 4015' - 4030', 4034' - 4039', 4069' - 4078', 4123' - 4132', 4170' - 4178', 4210' - 4224' and 4253' - 4262'.
Bridge plug at 4309'.
Casing leaks at unknown depths.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/20/2017 2:20 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 2294'. Ran tubing to 3971' and pumped 600 # gel followed by 90 sx cement w/350 # hulls. Pulled tubing to 3035' and pumped 150 sx cement w/250 # hulls. Pulled tubing to 1517' and pumped 170 sx cement w/200 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 15 sx cement. Connected to 8 5/8" surface casing and pumped 65 sx cement.

GPS: 39.97031N -101.14596W

Perfs:

Top	Bot	Thru	Comments
4253	4262		
4210	4224		
4170	4178		
4123	4132		
4069	4078		
4034	4039		
4015	4030		

KCC WICHITA
DEC 04 2017
RECEIVED

INVOICED
JAN 10 2018

Remarks: HURRICANE SERVICES INC. TICKET # 100840

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

NOV 22 2017