

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-21409-00-00
Spot: SENWSENE Sec/Twnshp/Rge: 29-1S-38W
1665 feet from N Section Line, 800 feet from E Section Line
Lease Name: BASH Well #: 1-29
County: CHEYENNE Total Vertical Depth: 5002 feet

Operator License No.: 30606 String Size Depth (ft) Pulled (ft) Comments
Op Name: MURFIN DRILLING CO., INC. PROD 5.5 4992 525 SX
Address: 250 N WATER STE 300 SURF 8.625 219 225 SX
WICHITA, KS 67202

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/21/2017 9:30 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 900 # gel and 800 # hulls.
8 5/8" surface casing set at 219' w/225 sx cement.
5 1/2" production casing set at 4993' w/525 sx cement.
TD 5002', PBTD 4963'.
Perforations: 4234' - 3203' and 4608' - 4620'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2017 1:35 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 4226' and pumped 900 # gel followed by 85 sx cement w/400 # hulls. Pulled tubing to 3186' and pumped 50 sx cement. Pulled tubing to 2373' and pumped 115 sx cement w/200 # hulls. Pulled tubing to 1185' and pumped 115 sx cement w/100 # hulls. Circulated cement to surface. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 20 sx cement. Connected to 8 5/8" surface casing and pumped 10 sx cement.

GPS: 39.94038N -101.60036W

Perfs:

Top	Bot	Thru	Comments
4608	4620		
4234	4240		

KCC WICHITA
DEC 04 2017
RECEIVED

INVOICED
JAN 10 2018

Remarks: HURRICANE SERVICES INC. SERVICE RIG AND CEMENT PUMP TRUCKS TICKET # 100841

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

NOV 22 2017