

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-109-20031-00-00  
Spot: S2N2NENW Sec/Twnshp/Rge: 15-11S-32W  
350 feet from N Section Line, 3300 feet from E Section Line  
Lease Name: OAKLEY UNIT Well #: 4-1  
County: LOGAN Total Vertical Depth: 4698 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>30606</u>	PROD	5.5	4697		285 SX
Op Name: <u>MURFIN DRILLING CO., INC.</u>	SURF	8.625	254		250 SX
Address: <u>250 N WATER STE 300</u> <u>WICHITA, KS 67202</u>					

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/29/2017 10:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 900 # gel and 1000# hulls.  
8 5/8" surface casing set at 254' w/250 sx cement.  
5 1/2" production casing set at 4697' w/285 sx cement.  
TD 4698', PBTD 4403'.  
Perforations: 4212' - 4216', 4242' - 4249', 4263' - 4267', 4294' - 4304', 4326' - 4330' and 4366' - 4370'.  
Well Depleted.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/29/2017 1:30 PM KCC Agent: DARREL DIPMAN

**Actual Plugging Report:**

Perforated production casing at 2580' and 1702'. Ran tubing to 4189' and pumped 900 # gel followed by 80 sx cement w/350 # hulls. Pulled tubing to 2587' and pumped 125 sx cement w/400 # hulls. Pulled tubing to 1293' and pumped 125 sx cement w/250 # hulls. Cement to surface. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 12 sx cement. Connected to 8 5/8" surface casing and pumped 15 sx cement.

GPS: 39.10381N -100.86114W

**Perfs:**

Top	Bot	Thru	Comments
4366	4370		
4326	4330		
4294	4304		
4263	4267		
4242	4249		
4212	4216		

KCC WICHITA  
DEC 04 2017  
RECEIVED

INVOICED  
JAN 10 2018

Remarks: HURRICANE SERVICES INC. SERVICE UNIT. HURRICANE SERVICES INC. CEMENT TICKET # 10,846

Plugged through: TBG

District: 04

Signed

*Darrel Dipman*

(TECHNICIAN)

CM

NOV 30 2017