

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-01566-00-00  
Spot: W2W2SE Sec/Twnshp/Rge: 31-9S-23W  
1320 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: HOOF NW LKC UNIT Well #: 104W  
County: GRAHAM Total Vertical Depth: 3983 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3977		100 SX
SURF	8.625	184		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/22/2017 8:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 470 sx 60/40 pozmix 4% gel cement w/700 # hulls.  
DV Tool at 2008' w/400 sx cement.  
Production perforations: 3863' - 3983'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/22/2017 10:45 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3773' and pumped 75 sx cement w/350 # hulls. Pulled tubing to 2993' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1920' and pumped 200 sx cement w/100 # hulls to circulate cement to surface. Pulled all tubing. Topped off 5 1/2" casing with 20 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 20 sx cement. Shut in pressure 150 psi.

GPS: 39.22265N -099.93048W

Perfs:

Top	Bot	Thru	Comments
3977	3983		
3960	3964		
3942	3945		
3863	3866		

Remarks: SWIFT SERVICES TICKET # 30873

Plugged through: TBG

District: 04

Signed

*Pat Bedore*

(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

DEC 20 2017

CONSERVATION DIVISION  
WICHITA, KS

NOV 29 2017

Form CP-2/3

INVOICED  
JAN 10 2018