

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20500-00-00
Spot: NWSESENW Sec/Twnshp/Rge: 2-34S-20W
3252 feet from S Section Line, 3292 feet from E Section Line
Lease Name: BAKER TRUST Well #: 2
County: COMANCHE Total Vertical Depth: 5250 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 88 INVERNESS CIR E. UNIT F104
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4150		WITH 2 SX CMT
CIBP		4250		
PROD	4.5	4874	2175	WITH 300 SX CMT
SURF	8.625	755		WITH 500 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2017 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4140' WITH 2 SX CMT. CUT & RECOVER CASING. TBG TO 800'. PUMP 10 SX GEL & 60 SX CMT. PULL TO 300' & PUMP 30 SX CMT. PULL TO 40' & PUMP 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: NONE
Date/Time Plugging Completed: 12/06/2017 12:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SET CIBP @ 4150' WITH 2 SX CMT. 1ST PLUG AT 790' WITH 10 SX GEL & 60 SX CMT. 2ND PLUG AT 315' WITH 30 SX CMT. 3RD PLUG AT 60'. CIRCULATED TO SURFACE WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4193	4199		

INVOICED
JAN 10 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: TBG

District: 01

Signed _____

[Signature]
5A (TECHNICIAN)

RECEIVED
DEC - 8 2017
KCC DODGE CITY *[Signature]*