

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-20503-00-00
Spot: NESWNWNE Sec/Twnshp/Rge: 2-34S-20W
4555 feet from S Section Line, 2130 feet from E Section Line
Lease Name: ORA BAKER Well #: 2
County: COMANCHE Total Vertical Depth: 4831 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 88 INVERNESS CIR E. UNIT F104
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3030		WITH 2 SX CMT
CIBP		3130		
PROD	5.5	4830	2550	WITH 200 SX CMT
SURF	8.625	673		WITH 450 SX CMT

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 12/08/2017 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 3130' WITH 2 SX CMT. RUN TBG TO 850' WITH 10 SX GEL & 40 SX CMT. PLUG AT 700' WITH 50 SX CMT. PLUG AT 300' WITH 30 SX CMT. PLUG AT 0-40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: NONE
Date/Time Plugging Completed: 12/08/2017 10:15 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CASING LEAK SQUEEZED AT 3125'-3197' WITH 350 SX CMT. SET CIBP @ 3030' WITH 2 SX CMT. 1ST PLUG AT 849' WITH 10 SX GEL & 40 SX CMT. 2ND PLUG AT 690' WITH 50 SX CMT. 3RD PLUG AT 295' WITH 30 SX CMT. 4TH PLUG AT 65' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3080	3130		

INVOICED
JAN 10 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed _____
(TECHNICIAN)

RECEIVED
DEC - 8 2017
KCC DODGE CITY