

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22635-00-02
Spot: N2S2SENV Sec/Twnshp/Rge: 29-33S-13W
2997 feet from S Section Line, 3318 feet from E Section Line
Lease Name: OLIVER BELL Well #: 2
County: BARBER Total Vertical Depth: 4845 feet

Operator License No.: 32811
Op Name: OSAGE RESOURCES, LLC
Address: PO BOX 1185
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		800		WITH 2 SX CMT
CIBP		3950		WITH 2 SX CMT
CIBP		4690		
PROD	4.5	4835	0	WITH 240 SX CMT
SURF	10.75	266		WITH 230 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/14/2017 8:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: JD DUBWIG Company: OSAGE RESURCES Phone: (620) 930-8056

Proposed Plugging Method: Confirm CIBP at 4690' and dump bail 10' cement on top. Set CIBP at 3950' and dump bail 10' cement on top. Test casing to 300 psi. Perforate squeeze holes at 650' and circulate cement plug inside and outside of 4-1/2" from 650' to surface. Cut off wellhead 3' below ground level, weld on steel plate and restore location.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: PARTIAL
Date/Time Plugging Completed: 11/22/2017 9:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

**CIBP @ 4690' & 2 SX CMT WAS PREVIOUSLY SET ON 9/6/07. ** 11/14/17: WAS UNABLE TO GET TOOLS BELOW 3965' SET CIBP @ 3950' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. FOUND FLUID LEVEL AT 380'. PRESSURE TESTED 4 1/2" CASING TO 300#. TEST WAS UNSATISFACTORY. SET CIBP @ 800' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PRESSURE TEST 4 1/2" CASING TO 310#. HELD. PERFORATE 4 1/2" CASING AT 650'. PUMPED DOWN 4 1/2" CASING WITH WATER. BROKE CIRCULATION. SHUT DOWN. 11/21/17: PUMP 225 SX CMT. CMT DID CIRCULATE. HOLE STAYING FULL. 11/22/17: CMT DOWN 120'. TOP OFF WITH READY MIX.

Perfs:

Top	Bot	Thru	Comments
4716	4768		
4048	4052		UPPER DOUGLAS
3984	3994		

INVOICED
JAN 10 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)
SA

RECEIVED
NOV 29 2017
KCC DODGE CITY