

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-179-21376-00-00
Spot: SENWSWSW Sec/Twnshp/Rge: 14-10S-29W
661 feet from S Section Line, 370 feet from W Section Line
Lease Name: BIXENMAN Well #: 1
County: SHERIDAN Total Vertical Depth: 4650 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4648		190 SX
SURF	8.625	256		185 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2017 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GLENN DINKEL Company: PALOMINO PETROLEUM, INC. DB Phone: (316) 799-1000

Proposed Plugging Method:
Stage Collar at 2394' w/200 sx cement.
Production perforations: 3987' - 4193'.
Ordered 450 sx 60/40 pozmix 4% gel cement, 900 # gel and 600 # hulls.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/05/2017 3:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3928'. Swift Services pumped 900 # gel followed by 80 sx cement w/400 # hulls.
Pulled tubing to 2412' and pumped 225 sx cement. Cement circulated. PTOH. Topped 5 1/2"
casing off with 20 sx cement. Casing full. Hooked up to backside and pumped 15 sx cement.
Maximum pressure 300 psi. Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
4190	4193		
4035	4038		
4026	4028		
4016	4018		
3987	3995		

Remarks:

Plugged through: TBG

District: 04

Received
KANSAS CORPORATION COMMISSION

Signed

Richard Williams

(TECHNICIAN)

CM

DEC 11 2017

DEC 20 2017

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3