

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25617-00-00
Spot: SWSWSENE Sec/Twnshp/Rge: 6-20S-25W
2430 feet from N Section Line, 1130 feet from E Section Line
Lease Name: LEWIS-FIELDS Well #: 1
County: NESS Total Vertical Depth: 4630 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		1722		CEMENTED WITH 135 SX CMT. 15 SX CMT CIRCULATED TO PIT
PROD	5.5	4629	0	WITH 175 SX CMT
SURF	8.625	219		WITH 165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/04/2017 1:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Revd. from: GLENN DINKEL Company: PALOMINO PETROLEUM Phone: (316) 799-1000

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 35 SX CMT & 150# HULLS. PULL TBG TO 1750' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 12/04/2017 3:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4446' & SPOT 35 SX CMT & 100# HULLS. PULL TBG TO 1740' & PUMPED 170 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 300#. HELD.

Perfs:

Top	Bot	Thru	Comments
4490	4493		

INVOICED
JAN 10 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed Michael Maier
(TECHNICIAN)

5A