

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-21440-00-00  
Spot: NENENE Sec/Twnshp/Rge: 28-30S-6W  
330 feet from N Section Line, 330 feet from E Section Line  
Lease Name: REIDA "B" Well #: 2  
County: KINGMAN Total Vertical Depth: 4185 feet

Operator License No.: 5123  
Op Name: PICKRELL DRILLING COMPANY, INC.  
Address: 100 S MAIN STE 505  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4183		200 SX
SURF	8.625	259		185 SX

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/22/2017 8:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: DAVID HOMMERTZHEIM Company: \_\_\_\_\_ Phone: (620) 793-2316

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/22/2017 1:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 3700' & CAPPED WITH 2 SKS CEMENT. CASING WAS RECOVERED FROM 2400' & PULLED FROM WELL. TABING WAS RUN TO 1250' WHERE 15 SX OF GEL & 50 SX OF CEMENT WAS SPOTTED. TAGGED CEMENT AT 921'. RAN TUBING BACK IN HOLE TO 744' WHERE 30 SX OF CEMENT WAS SPOTTED. PULLED TUBING TO 310' & CIRCULATED. CEMENT TO SURFACE WITH 120 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4108	4112	TBG	

INVOICED  
JAN 10 2018

Remarks: BASIC SERVICES DENIED TA

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)