

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-20617-00-00
Spot: SENE Sec/Twnshp/Rge: 28-30S-6W
3300 feet from S Section Line, 660 feet from E Section Line
Lease Name: REIDA B Well #: 1
County: KINGMAN Total Vertical Depth: 4524 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4233	2210	125 SX
SURF	8.625	209		160 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/27/2017 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BERRY WALTERS Company: ALLIANCE WELL SERVICE Phone: (620) 793-2316

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/29/2017 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 4090' & CAPPED WITH 2 SKS CEMENT. THE CASING WAS RECOVERED FROM 2210' & PULLED FROM WELLBORE. TUBING WAS RUN TO 1194' WHERE 12 SX GEL & 50 SX OF CEMENT WAS SPOTTED. PULLED TUBING TO 700' WHERE 30 SX OF CEMENT WAS SPOTTED. PULLED TUBING TO 264' WHERE CEMENT WAS CIRCULATED TO SURFACE WITH 90 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4143	4148		

INVOICED
JAN 10 2018

Remarks: BASIC SERVICES. COMMON CEMENT 3% CACL. DENIED TA

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)