



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Mont Ottinger of Summons Drilling Inc has this date requested permission to plug the following described well:

Operator's Full Name: Voyager Petroleum Inc

Complete Address: 110-16th St Denver, Colorado

Lease Name: Miller Well No. # 9-13

Location: W 1/2 - SW - SW Sec. 9 Twp. 20 Rge. 20^W (E) (W)

County: Pawnee Total Depth: 4401^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Ottinger was instructed to plug the well as follows

8 5/8" 240 Et SP. cur w/ 160st Halliburton 2% Gel.

Order 115st 50/50 Poz mix 4% Gel - 3% CaCl. + 8 5/8" Plug

Spot with Drill Stem - with Heavy mud Between all Plugs.

1st Plug - @ 740^{FE} w/ 65st cur.

2nd Plug - @ 270^{FE} w/ 30st cur

3rd Plug - solid bridge - plug @ 40^{FE} w/ 10st cur.

5th In Rat Hole.

5th In mouse hole.

Very truly yours, (By Halliburton Cur)

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1981

6-29-81
CONSERVATION DIVISION
Wichita, Kansas

Marius Schmidt
Conservation Division Agent