

State of Kansas



15.145.30096.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 31 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Cameron of H-30 Drilling co. has this  
date requested permission to plug the following described well:

Mr. Cameron guarantees payment of the plugging fee.

Operator's full Name: Petroleum Operating Co.

Complete Address: 6045 Pine Tree Drive Miami Beach, Florida

Lease Name: Kurt Well No. 1

Location: SW- NW- Sec. 27 Twp. 20 Rge. 19 (E)(W) X

County Pawnee Total Depth 4380 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cameron was instructed to plug the well as follows:

Gum pits, circulate heavy mud, set cementing plug at 540 Ft.

and displace 25 sax cement thru drill pipe. heavy mud to 375 ft.

set cementing plug and displace 20 sax cement thru drill pipe.

heavy mud to 40 Ft. and build solid bridge of cementing plug,

1/3 sax hulls and 10 sax cement to base of celar. Plug rat hole

with 2 sax cement.

Very truly yours,

[Signature]  
Conservation Division Agent