

To: 1 121103  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 145-21,218.0000

N/2 N/2 NW, SEC. 23, T 20 S, R 20 W/E  
4950 feet from S section line  
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT *1-25*

Operator License # 4058

Lease Name Jennings Well # 2

Operator: American Warrior, Inc.

County Pawnee

Name & Address P.O. Box 399

Well Total Depth 4328 *140.66* feet

Garden City, KS 67846

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 531

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Southwest Supply Co. License Number \_\_\_\_\_

Address Garden City, KS

Company to plug at: Hour: 11 a.m. Day: 25 Month: 1 Year: 19 96

Plugging proposal received from Scott Corsair

(company name) American Warrior, Inc. (phone) 913-398-2270

logs: 5 1/2" at 4327' w/500 sx cement, PBTD 4210', Perfs at 4277-82'

1st plug spot 50 sx cement at 1300', 2nd plug spot 50 sx cement at 580',

3rd plug spot 50 sx cement at 400', 4th plug spot 10 sx cement at 40-0'.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 25 Month: 1 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug shot casing at 765' and pumped 10 sx gel, 60 sx cement, and displaced with gel,

2nd plug pulled casing to 400' and circulated with 90 sx cement,

3rd plug laid down all casing and topped off with 10 sx cement.

NOTE: 5 1/2" bridged over at 790'-unable to remove with tools.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 765' of 5 1/2" casing. (if additional description is necessary, use BACK of this form.)

**INVOICED**

(did / ~~not~~) observe this plugging.

DATE 2-2-96

Signed *David Rabin* (TECHNICIAN)

INV. NO. 44788

RECEIVED  
KANSAS CORPORATION  
JUN 3 11 58 AM '96  
1-31-96