

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21165-00-00  
Spot: CN2NWNW Sec/Twnshp/Rge: 23-20S-20W  
4950 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: JENNINGS Well Number: 1  
County: PAWNEE Total Vertical Depth: 4365 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: PO BOX 399  
GARDEN CITY, KS 67846

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 565 WITH 250 SX CMT  
Production: Size 5.5 feet: 4361 WITH 500 SX CMT  
Liner: Size \_\_\_\_\_ feet: 8/41.86

Well Type: EOR UIC Docket No: E24252.1 Date/Time to Plug: 07/17/2001 12:30 PM

Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: SCOTT CORSAIR Company: AMERICAN WARRIOR Phone: (785) 398-2270

Proposed Plugging Method: RUN TUBING TO 2880' & PUMP 30 SX CMT & 100# HULLS. PERFORATE AT 590'. PUMP 5 BBLs WATER DOWN CASING. PUMP 170 SX CMT DOWN CASING.

Plugging Proposal Received By: STEVE DURRANT  
Date/Time Plugging Completed: 07/17/2001 2:45 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4320'. PERFS AT 4294-4320'. RUN TUBING TO 2880' PUMP 30 SX CMT & 100# HULLS. PERFORATE CASING AT 590'. PUMPED 5 BBLs WATER DOWN 5 1/2" CASING HAD CIRCULATION. PUMPED 170 SX CMT DOWN 5 1/2" CASING. CIRCULATED 10 SX CMT TO PIT.

RECEIVED  
KANSAS CORPORATION COMMISSION  
AUG 01 2001  
CONSERVATION DIVISION

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

INVOICED  
DATE 8-01-01  
INV. NO. 2002060157

District: 01

Signed Michael Maier  
(TECHNICIAN)

JUL 18 2001

Form CP-28