

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21437-00-00  
Spot: E2NENE Sec/Twnshp/Rge: 2-20S-20W  
4620 feet from S Section Line, 400 feet from E Section Line  
Lease/Unit Name: SELTMAN Well Number: 1  
County: PAWNEE Total Vertical Depth: 4330 feet

Operator License No.: 5015  
Op Name: HELLAR DRILLING COMPANY, INC.  
Address: 400 N WOODLAWN SUITE 16  
WICHITA, KS 67208

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 538 WITH 250 SX CMT <sup>\$/40.73</sup>  
Production: Size 5.5 feet: 4328 WITH 125 SX CMT  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/08/2001 9:30 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND IN TO 4160' WITH 5 SX CMT. 1ST PLUG AT 1450' WITH 50 SX CMT & 15 SX GEL. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/08/2001 12:05 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PERFS AT 4216-20'. SAND TO 4160' & 5 SX CMT WITH A DUMP BAILER. 1ST PLUG AT 1475' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2430' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED

OCT 16 2001  
10-16-01  
KCC WICHITA

INVOICED OCT 12 2001

DATE 10-16-01  
INV. NO. 2002060812

Form 10-2/3