

1080512

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,203.0001  
C NE NE, SEC. 27, T 20 S, R 19 W/EX  
4620 feet from S section line  
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4340

Lease Name Seltman Et Al Well # 1

Operator: Jayco Resources, Inc.

County Pawnee 140.08

Name & Address 14925 Memorial Drive, Suite 108  
Houston, TX 77079

Well Total Depth 4310 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 451

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address P. O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1:15 pm Day: 10 Month: April Year: 19 86

Plugging proposal received from Brad Siroky

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 4 1/2" at 4303' Perfs at 4247-48'; 4250-56'

1st plug sand back to 4200' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:15 pm Day: 10 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx cement.

Maximum pressure 500 psi and shut in 100 psi

RECEIVED  
STATE CORPORATION COMMISSION  
APR 16 1986  
4-16-86  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Recovered 2935' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

~~INVOICED~~ Observe this plugging.

DATE APR 16 1986

Signed J. N. Mead  
(TECHNICIAN)

INV. NO. 13463