

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County. Sec. 31 Twp. 20 Rge. 19W (E) (W)

Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE

Lease Owner Murfin & Aurora

Lease Name Alexander Well No. 1

Office Address 507 Union Nat. Bank Bldg - Wichita, Ks.

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed 3-7 1956

Application for plugging filed 3-7 1956

Application for plugging approved 3-7 1956

Plugging commenced 3-7 1956

Plugging completed 3-7 1956

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Plugging Agent who supervised plugging of this well R. M. Brundage

Producing formation Depth to top Bottom Total Depth of Well 4753 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	228	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud laden fluid.
Plugged hole with 100 sx. cement by Sun Cementing Co.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Murfin Drilling Co.

Address 507 Union Nat. Bank Bldg - Wichita, Ks.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Murfin (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *WR Murfin*

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of March, 1956.

My commission expires 6-13-59.

Betty Spriggs
Notary Public.

PLUGGING
FILE SEC. 31 T. 20 R. 19W
BOOK PAGE 44 LINE 43

APR 4 - 1956
4-4-56
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

15.145.00130.0000

COMPANY Murfin & Aurora

SEC. 31 T. 20 R. 19W

FARM Alexander NO. 1

LOC. NE NE NE

TOTAL DEPTH 4753

COMM. 2-14-56


COMP. 3-7-56

COUNTY Pawnee
KANSAS

SHOT OR TREATED

CONTRACTOR Murfin Drlg. Co.

ISSUED



CASING

20	10	
15	8	228' w/175 sx.
12	6	
13	5	

ELEVATION 2201 DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

45 Post Rock - Shale
 330 Shale - Shells
 380 Sand
 585 Shale - Shells
 750 Red Bed - Shale
 950 Sand
 1375 Red Bed - Shells
 1405 Anhydrite
 1770 Red Rock - Shale - Shells
 1815 Shale - Shells
 1940 Salt - Shale
 2050 Shale - Lime - Shells
 2205 Shale - Shells
 3580 Lime - Shale
 3750 Lime
 3842 Lime - Shale
 4072 Lime
 4105 Lime - Shale
 4150 Lime
 4330 Shale - Lime
 4360 Shale - Sand - Lime
 4388 Shale - Miss Chert
 4440 Chert - Lime - Shale
 4465 Lime - Shale
 4490 Lime
 4501 Sand
 4519 Sand - Shale - Lime
 4534 Sand (Hard) - Shale
 4640 Lime - Shale
 4753 Lime

Tops: (Schlum)

Heebner 3747
 Toronto 3770
 Lansing 3800
 Base KC 4144
 Cherokee shale 4277
 Cherokee sand 4310
 Mississippian 4370
 Miss. lime 4449
 Kinderhook 4484
 Viola 4533

4753 RTD

RECORDED
STATE DEPARTMENT OF REVENUE

PLUGGING
 FILE SEC 31 T 20 R 19W
 BOOK PAGE 44 LINE 43

State of Kansas
 County of Sedgwick

APR 1 1956
 SS: [Signature]

I, W. R. Murfin of the Murfin Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Alexander #1 well.

WR Murfin

Subscribed and sworn to before me this 20th day of March 19 56.

My Commission Expires: 6-13-59.

Betty Spriggs
 NOTARY PUBLIC