


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County. Sec. 29 Twp. 20S Rge. (E) 19W (W)

Location as "NE/CNW/SW" or footage from lines NE NW NW
Lease Owner R. W. Shields
Lease Name Brannon Well No. 1
Office Address 308 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 13, 1961
Application for plugging filed April 13, 1961
Application for plugging approved April 13, 1961
Plugging commenced April 13, 1961
Plugging completed April 13, 1961
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Depth to top Bottom Total Depth of Well 4300 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud from 4300' to 300'. Set Plug No. 1 at 300' with 20 sacks cement. Filled hole with mud to 35'. Set Plug No. 2 at 35' with 10 sacks cement. Filled hole with cement to bottom of cellar. Put two sacks cement in rat hole. Plugging completed at 5:00 A.M. of April 13, 1961.

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1961
4-28-61
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Barnett Drilling, Inc. (If additional description is necessary, use BACK of this sheet)
Address 409 First National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK
Jack S. Griggs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack S. Griggs
409 First Nat'l Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of April, 1961

My commission expires November 26, 1962.

Louise F. Whitted
Notary Public.

BARNETT DRILLING, INC.
 LOG OF BRANNON NO. 1
 NE NW NW SEC. 29-20S-19W
 PAWNEE COUNTY, KANSAS

Commenced: 4/1/61

Completed: 4/13/61

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	20	Ran 405' of 8-5/8" 28# Used Casing; cemented w/250 sax HA-5
Post Rock	20	50	
Shale	50	90	
Shale & Shell	90	220	
Sand	220	250	
Shale & Shell	250	405	
Shale	405	640	
Red Bed	640	760	
Sand	760	890	
Shale & Shell	890	1100	
Shale, Shell & Red Bed	1100	1345	
Anhydrite	1345	1380	
Shale & Shell	1380	2240	
Lime & Shale	2240	2485	
Lime	2485	2570	
Lime & Shale	2570	2835	
Shale & Lime	2835	2970	
Lime & Shale	2970	3050	
Shale & Lime	3050	3225	
Lime & Shale	3225	3345	
Lime	3345	3565	
Lime & Shale	3565	3815	
Lime	3815	4225	
Sand	4225	4230	
Lime	4230	4300'	T. D. D&A

RECEIVED
 STATE CORPORATION COMMISSION

APR 28 1961

CONSERVATION DIVISION
 Wichita, Kansas

I, Jack S. Griggs, of Barnett Drilling, Inc. certify to the best of my knowledge and belief that the foregoing is a true and correct log of the Brannon No. 1, located in the NE NW NW of Section 29-29S-19W, Pawnee County, Kansas.

Jack S. Griggs

Subscribed and sworn to by and before me in and for the County of Sedgwick, State of Kansas on this 17th day of April, 1961.

Louise K. Whitted
 Louise K. Whitted - Notary Public

My Commission expires November 26, 1962.