


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Pawnee County. Sec. 27 Twp. 20 Rge. 19 (EX) (W)
Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner Petroleum Operating Co.
Lease Name Kurt Well No. 1
Office Address 6045 Pine Tree Drive, Miama, Florida
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed May 29 19 66
Application for plugging filed May 29 19 66
Application for plugging approved May 29 19 66
Plugging commenced May 29 19 66
Plugging completed May 29 19 66
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	388.25'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4380' (rotary total depth) to 540'. Set bottom plug @ 540' and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 375' and cemented with 20 sacks cement. Filled hole with heavy rotary mud to 40'. Set top plug @ 40' and cemented with 10 sacks cement, 2 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

JUN -2 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.
Address 200 North Main, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Merle Britting (Employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Merle Britting
200 North Main, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of June, 19 66

My commission expires December 27, 1967

Maxine Lampe
Notary Public.

15.145.30096.0000

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY Petroleum Operating Co.


SEC. 27 T. 20S R. 19W
 LOC. C SW NW

FARM Kurt NO. 1

TOTAL DEPTH 4380'
 COMM. 5/18/66 COMP. 5/29/66
 SHOT OR TREATED
 CONTRACTOR H-30, Inc.
 ISSUED

COUNTY Pawnee

KANSAS



CASING

20 10
 15 8 - 5/8" @ 388.25 w/250 sx. cement
 12 6
 13 5

ELEVATION 2228 KB

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay	150
Sand	172
Shale	389
Shale, Shells & Red Bed	780
Sand	950
Shale & Shells	1325
Red Bed & Shale	1379
Anhydrite	1407
Shale & Lime Shells	1530
Shale	1730
Shale & Lime Streaks	2125
Lime & Shale	2303
Lime	2660
Broken Lime	2780
Lime & Shale	3545
Lime	3631
Lime & Shale	3773
Lime	4257
Lime & Sand with Shale	4352
Lime	4380
Rotary T. D.	4380

ELECTRIC LOG TOPS

Heebner	3742	-1514
Lansing	3792	-1564
Base KC	4154	-1926
Cherokee	4257	-2029
Shaley Sand	4285/4290	-2057/-2062
Sand	4293/4304	-2065/2076
Sand	4310/4314	-2082/-2086
Sand	4319/4326	-2091/-2098
Sand	4340/4352	-2112/-2124
Mississippi	4360	-2132
Log T. D.	4379	-2151
Rotary T. D.	4380	-2152

RECEIVED
 STATE CORPORATION COMMISSION

JUN -2 1966

CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well, as shown by the drilling reports.

H-30, INC.

Merle Britting
 Merle Britting

STATE OF KANSAS)
) ss
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 1st day of June, 1966.

My Commission Expires:
 December 27, 1967

Maxine Lampe
 Maxine Lampe - Notary Public