

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-21,571-0000

LEASE NAME McCreight

WELL NUMBER A-1

 Ft. from S Section Line

 Ft. from E Section Line
 SW SW SW

SEC. 10 TWP. 20S RGE. 23W (E) or (W)

COUNTY Ness

Date Well Completed

Plugging Commenced 12-16-86

Plugging Completed 12-22-86

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Donald C. Slawson

ADDRESS 200 Douglas Bldg. Wichita, Kansas 67202

PHONE# (316) 263-3201 OPERATORS LICENSE NO. 5181

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4483'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	505'	none
				4-1/2"	4482'	2847'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand to 4345' and 4 sacks cement. Shot pipe @3026', 2847', pulled a total of 68 joints of 4-1/2" casing. Plugged surface with 3 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug and 150 cement, 60/40 pos, 6% gel.
Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

DEC 30 1986

R. Darrell Kelso, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 29th day of December, 19 86

[Signature]
 Notary Public

My Commission Expires:



KANSAS DRILLERS LOG

API No. 15 — 135 — 21,571
 County Number

S. 10 T. 20 R. 23W E
 W
 Loc. SW SW SW


Operator DONALD C. SLAWSON

County Ness

Address 200 Douglas Building Wichita, Kansas 67202

640 Acres
N

Well No. 1 Lease Name McCreight 'A'



Footage Location 330 feet from X (S) line 340 feet from X (W) line

Elev.: Gr. 2268

Principal Contractor Slawson Drilling Co., Inc. Geologist George Mueller

Spud Date January 8, 1979 Total Depth 4483 P.B.T.D. 4432

Date Completed January 20, 1979 Oil Purchaser Koch

DF 2270 KB 2273

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (In O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	505'	60/40 poz	350 sx	2% gel, 3% cc
Production	7 7/8"	4 1/2"	10.5#	4482'	Neat 50/50 poz	25 sx 100 sx	18% salt, 3/4 1% CFR-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	Jet	4395-97

TUBING RECORD

Size	Setting depth	Packer set at
2 3/8	4400	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

INITIAL PRODUCTION

Date of first production 2/16/79 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	78 bbls.	None MCF	48 bbls.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval(s) 4395-97

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.